

TRINITY COURT CONDITIONAL ZONING PERMIT

CHAPEL HILL - TRINITY COURT
751 TRINITY CT, CHAPEL HILL, NC 27516

C - SERIES DRAWING ABBREVIATIONS:

- | | |
|---|----------------------------------|
| ADV - ADVANCE | MIN - MINIMUM |
| AFG - ABOVE FINISHED GRADE | MIN S - MINIMUM SLOPE |
| APPR LOC - APPROXIMATE LOCATION | ML - MECHANICAL JOINT |
| ASSY - ASSEMBLY | NIC - NOT IN CONTRACT |
| B/C - BACK OF CURB | NIS - NOT TO SCALE |
| BL - BASE LINE | ONE - OVERHEAD ELECTRIC |
| BS - BOTTOM OF STAIR | OPR - OVERHEAD POWER |
| B/W - BOTTOM OF WALL | OHT - OVERHEAD TELEPHONE |
| CS - CAST BASIN | PI - PLUMB |
| CBR - CALIFORNIA BEARING RATIO | PC - POINT OF CURVATURE |
| CG - CURB AND GUTTER | PE - PEDESTAL |
| CL - CENTERLINE | PG - PAGE |
| CL - CLASS | PH - PHASE |
| CM - CONCRETE MONUMENT | PI - POINT OF INTERSECTION |
| CMP - CORRUGATED METAL PIPE | PKG - PARKING |
| CO - CLEAN OUT | PL - PROPERTY LINE |
| CONC - CONCRETE | PT - POINT OF TANGENT |
| CONN - CONNECTION | PP - POWER POLE |
| CP - CORRUGATED PLASTIC | PVC - POLYVINYL CHLORIDE |
| CY - CUBIC YARD | PW - PAVEMENT |
| DB - DEBRIS BOX | PWR - POWER |
| DL - DROP INLET | RE - RECORDED METES & BOUNDS |
| EP - ELECTRIC PIPE | RD - ROOF DRAIN |
| D.M.P. - DOUBLE MERIDIAN DISTANCES | RJ - REINFORCED JOINT |
| EPC - DRIVE | R/W - RIGHT-OF-WAY |
| DS - DOWNSPOUT | REQD - REQUIRED |
| E - ELECTRIC | RFC - REINFORCED CONCRETE PIPE |
| EA - EACH | S - SLOPE |
| E BOX - ELECTRICAL BOX | SAN - SANITARY SEWER |
| ELEC - ELECTRIC | SDW - SIDEWALK |
| EP - EDGE OF PAVEMENT | SF - SILT FENCE |
| ES - EDGE OF SHOULDER | SPT - SPOT GRADE |
| EX - EXISTING | SS - SANITARY SEWER CONNECTION |
| EX - EXISTING | STD - STANDARD |
| FD - FIRE DEPARTMENT CONNECTION | STM - STORM |
| FF - FINISHED FLOOR | STM-S - STORM SEWER MANHOLE |
| FHY - FIRE HYDRANT | T - TELEPHONE |
| FL - FLOOR LINE | TIC - TOP BACK OF CURB |
| FL - FIRE LANE | TOM - TELECOMMUNICATIONS MANHOLE |
| GS - GAS | TEL - TELEPHONE |
| MG - GAS METER | TIS - TOP OF STAIR |
| GI - GATE INLET | T/W - TOP OF WALL |
| GRND - GROUND | USE - UNDERGROUND ELECTRIC |
| GTS - GAS TEST STATION | UNK - UNKNOWN |
| GV - GAS VALVE | UP - UTILITY POLE |
| HORZ - HIGH DENSITY POLYETHYLENE | VAR - VARIABLE |
| HORIZ - HORIZONTAL | VDP - VITRIFIED CLAY PIPE |
| HVAC - HEATING, VENTILATION, & AIR CONDITIONING | VERT - VERTICAL |
| INV - INVERT | W - WITH |
| IPF - IRON PIPE FOUND | WL - WATER LINE |
| IRS - IRON PIPE SET | W - WATER |
| IRF - IRON ROD FOUND | WUS - WATERS OF THE US |
| LSA - LANDSCAPED AREA | XING - CROSSING |
| LF - LIGHT FEET | VI - VARD INLET |
| LP - LIGHT POLE | D - DIAMETER |
| MI - MEASURED METES & BOUNDS | |
| MECH - MECHANICAL | |
| MH - MANHOLE | |



VICINITY MAP
NOT TO SCALE

Sheet Number	Sheet Title
C0.0	COVER SHEET
C0.1	AREA MAP
C1.0	EXISTING CONDITIONS & DEMOLITION
C2.0	PHASE I EROSION & SEDIMENT CONTROL PLAN
C2.1	PHASE II EROSION & SEDIMENT CONTROL PLAN
C2.2	PHASE III EROSION & SEDIMENT CONTROL PLAN
C3.0	SITE PLAN
C3.1	UTILITY PLAN
C3.2	WATER LINE PROFILES
C3.3	SOLID WASTE MANAGEMENT PLAN
C4.0	GRADING AND DRAINAGE PLAN
C4.1	STEEP SLOPE PLAN
C4.2	STORM PROFILES
C5.0	NOTES AND DETAILS
C5.1	NOTES AND DETAILS
C5.2	NOTES AND DETAILS
C5.3	NOTES AND DETAILS
L1.0	LANDSCAPE PROTECTION PLAN
L1.1	LANDSCAPE PLAN
L1.2	LANDSCAPE DETAILS

LEGEND

- | | |
|------------------------|---|
| SEWER | EXISTING SANITARY SEWER |
| 8" SAN | SANITARY SEWER |
| N 7655.80
E 9378.25 | SANITARY MANHOLE NUMBER
W/ COORDINATE LOCATION |
| ○ | EX SANITARY MANHOLE |
| ⊙ | SANITARY MANHOLE |
| ○ | EXISTING CLEAN OUT |
| ○ | CLEAN OUT |
| WATER | EXISTING WATER LINE |
| 8" W | WATER LINE |
| ⊙ | EXISTING WATER VALVE |
| ⊙ | WATER VALVE |
| ⊙ | POST INDICATOR VALVE |
| ⊙ | EXISTING WATER METER |
| ⊙ | WATER METER |
| ⊙ | EXISTING FIRE HYDRANT |
| ⊙ | FIRE HYDRANT |
| ⊙ | WATER LINE REDUCER |
| ⊙ | EX WATER LINE PLUG |
| ⊙ | WATER LINE PLUG |
| ⊙ | WATER LINE CROSS |
| ⊙ | WATER LINE TEE |
| ⊙ | FIRE DEPT CONNECTION |
| ⊙ | WATER SPOUT |
| ⊙ | EXISTING WELL CASING |
| NATURAL GAS | EXISTING GAS METER |
| ⊙ | EXISTING GAS VALVE |
| ⊙ | EXISTING GAS LINE |
| ⊙ | GAS LINE |

MISCELLANEOUS UTILITIES

- | | |
|---|---------------------------------|
| ○ | EXISTING LIGHT POLE |
| ○ | EXISTING YARD LIGHT |
| ○ | EXISTING GROUND LIGHT |
| ○ | LIGHT POLES |
| ○ | EXISTING UTILITY POLE |
| ○ | UTILITY POLE |
| ○ | EXISTING GUY WIRE |
| ○ | EXISTING ELECTRIC METER |
| ○ | EXISTING OVERHEAD ELECTRIC |
| ○ | OVERHEAD ELECTRIC |
| ○ | EX UNDERGROUND ELECT LINE |
| ○ | UNDERGROUND ELECTRIC LINE |
| ○ | EXISTING TELEPHONE PEDESTAL |
| ○ | BENCH MARK |
| ○ | APPROX BORING LOCATION |
| ○ | OHT - OVERHEAD TELEPHONE LINE |
| ○ | EX UNDERGROUND TELEPHONE LINE |
| ○ | UNDERGROUND TELEPHONE LINE |
| ○ | EX OVERHEAD FIBER OPTIC LINE |
| ○ | OVERHEAD FIBER OPTIC LINE |
| ○ | EX UNDERGROUND FIBER OPTIC LINE |
| ○ | UNDERGROUND FIBER OPTIC LINE |
| ○ | EX CABLE TV PEDESTAL |
| ○ | EX OVERHEAD CABLE TV LINE |
| ○ | OVERHEAD CABLE TV LINE |
| ○ | EX UNDERGROUND CABLE TV |
| ○ | UNDERGROUND CABLE TV LINE |
| ○ | COMBINED POWER/CATV |
| ○ | COMBINED POWER, TELE, CATV |
| ○ | COMBINED TELEPHONE, CATV |

SITE

- | | |
|---|-----------------------------------|
| ○ | EXISTING STORM SEWER |
| ○ | STORM SEWER |
| ○ | EX DROP INLET |
| ○ | DROP INLET & STRUCTURE NUMBER |
| ○ | EXISTING STORM SEWER MANHOLE |
| ○ | STORM SEWER MANHOLE |
| ○ | EXISTING ROOF DRAIN DOWNSPOUT |
| ○ | ROOF DRAIN DOWNSPOUT |
| ○ | EXISTING CURB |
| ○ | CURB |
| ○ | EXISTING CURB & GUTTER |
| ○ | CURB & CUTTER |
| ○ | PROPERTY LINE |
| ○ | BENCH MARK |
| ○ | APPROX BORING LOCATION |
| ○ | EXISTING TREE LINE |
| ○ | CLEARING LIMITS |
| ○ | EXISTING SHRUB |
| ○ | EXISTING TREE |
| ○ | EXISTING FENCE |
| ○ | FENCE |
| ○ | EXISTING CONTOUR |
| ○ | CONTOUR |
| ○ | SPOT ELEVATION |
| ○ | CL SWALE |
| ○ | EXISTING SIGN |
| ○ | SIGN |
| ○ | BOLLARD |
| ○ | FLAG POLE |
| ○ | PROPERTY MARKER FOUND / ROD FOUND |
| ○ | PIPE FOUND |
| ○ | MONUMENT FOUND |

OWNER

TRINITY COURT REDEVELOPMENT, LLC
4915 RADFORD AVE, SUITE 300
RICHMOND, VA 23230
CONTACT: SAMANTHA BROWN
PHONE: (804) 614-2682
FACSIMILE: N/A

ARCHITECT


MOSELEY ARCHITECTS
1414 KEY HIGHWAY,
BALTIMORE, MD 21220
CONTACT: TOM LIEBEL
PHONE: (410) 539-4300
FACSIMILE: (410) 539-0660

SITE DEVELOPMENT

TIMMONS GROUP
5410 TRINITY ROAD, SUITE 102
RALEIGH, NORTH CAROLINA 27607
CONTACT: MR. WILL ALTMAN
PHONE: (919) 866-4938
FACSIMILE: (919) 859-5663

SITE DATA TABLE	
PROJECT NAME:	TRINITY COURT
PROJECT ADDRESS:	751 TRINITY COURT CHAPEL HILL, NC
TOTAL ACREAGE:	3.5 ACRES
FIN NUMBER:	278254511
ZONING:	R-4
USE:	AFFORDABLE HOUSING, MEDIUM DENSITY RESIDENTIAL
ONSITE IMPERVIOUS AREA EXISTING:	1,331 ACRES (60,037 SF)
ONSITE IMPERVIOUS PROPOSED:	1,339 ACRES (60,637 SF)
TOTAL DISTURBED AREA:	2,071 ACRES (90,419 SF)
REQUIRED PARKING:	
1 SPACE PER (1) BEDROOM DWELLING UNIT	
1.25 SPACE PER (2) BEDROOM DWELLING UNIT	
1.5 SPACE PER (3) BEDROOM DWELLING UNIT	
1 PARKING SPACE X 14 (1) BEDROOM DWELLING UNITS	
1.25 PARKING SPACE X 20 (2) BEDROOM DWELLING UNITS	
1.5 PARKING SPACE X 20 (3) BEDROOM DWELLING UNITS	
MINIMUM 64 PARKING SPACES	
REQUIRED ACCESSIBLE PARKING:	
MINIMUM OF 3 ACCESSIBLE PARKING SPACES FOR LOTS WITH BETWEEN 51 AND 75 PARKING SPACES	
PROVIDED PARKING:	64 PARKING SPACES PROVIDED; 3 ACCESSIBLE SPACES PROVIDED

MOSELEY ARCHITECTS
 1414 KEY HIGHWAY, BALTIMORE, MD 21220
 PHONE: (410) 539-4300 FAX: (410) 539-0660
 MOSELEYARCHITECTS.COM
TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516
COVER SHEET
 C0.0



LOCATION MAP

NOT TO SCALE
 PARCEL IDENTIFICATION NUMBER (PIN) 978194311
 ADDRESS: 751 TRINITY CT, CHAPEL HILL, NC 27516

LEGEND

	PROPOSED SITE PROPERTY LINE
	ZONING BOUNDARY
	CHAPEL HILL TOWN LIMITS
	NORTHSIDE OVERLAY ZONING DISTRICT
	100' NOTIFICATION AREA
	PROPOSED SITE

NOTES:
 1. ENTIRETY OF SITE AREA IS LOCATED WITHIN CHAPEL HILL'S TOWN LIMIT



SCALE 1"=150'
 0 150 300


MOSELEYARCHITECTS
 1414 KEY HIGHWAY, BALTIMORE, MD 21220
 PHONE (410) 539-2500 FAX (410) 533-0666
 MOSELEYARCHITECTS.COM



TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

PROJECT NO.	DATE
0001	DECEMBER 8, 2021
REVISIONS	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-

AREA MAP
C0.1



LIMITS OF DISTURBANCE: 2.08 ± AC

EROSION CONTROL LEGEND

- TEMPORARY CONSTRUCTION ENTRANCE
- SILT FENCE
- DUST CONTROL
- LINE OF DISTURBANCE
- TEMPORARY DIVERSION
- STAGING AREA
- TREE PROTECTION
- SILT FENCE OUTLET
- INLET PROTECTION
- SLOPE MATTING
- DIVERSION

SILT FENCE OUTLETS ARE TO BE PROVIDED ALONG ALL LOW POINTS OF SILT FENCE AND AREAS WHERE RUNOFF MAY CONCENTRATE CAUSING DAMAGE TO SILT FENCE. CONTRACTOR TO INSTALL OUTLETS AS NECESSARY TO ENSURE SILT FENCE IS FULLY FUNCTIONAL THROUGHOUT THE DURATION OF CONSTRUCTION.

NOTE: THE NPDES CONSTRUCTION PERMIT REQUIRES EROSION CONTROL DEVICES AND STORM WATER OUTFALLS BE INSPECTED WEEKLY (EVERY 7 CALENDAR DAYS) AND WITHIN 24 HRS OF A 2 INCH RAIN EVENT. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT THESE INSPECTIONS AND MAINTAIN RECORDS UNTIL THE AREA HAS STABILIZED. EVIDENT BY 95% VEGETATIVE GROWTH FOR AREAS PROVIDED SEEDING. TO FACILITATE RAINFALL MONITORING A RAIN GAUGE IS REQUIRED TO BE ON SITE. ADDITIONALLY THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING SELF INSPECTIONS INDICATING THE DATE WHEN ARE INSTALLED AND STABILIZATION MEASURES (SEEDING/MULCHING OR SOIL) ARE INITIATED. THE "SELF INSPECTION" REPORTS WILL BE MAINTAINED ALONG WITH THE "NPDES INSPECTION REPORTS". ONCE STABILIZATION HAS BEEN ACCOMPLISHED INSPECTION RECORDS ARE TO BE FORWARDED TO EAO AND ALL TEMPORARY EROSION/SEDIMENT CONTROL DEVICES REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING COMPLIANCE WITH ALL PERMITS AND PLANS. ANY CHANGES WILL BE APPROVED BY THE STATE PRIOR TO EXECUTION. A COPY OF THE EROSION AND SEDIMENTATION CONTROL PLAN, LETTER OF APPROVAL AND NPDES CONSTRUCTION PERMIT WILL BE MAINTAINED BY THE CONTRACTOR AT THE ON-SITE OFFICE. IF SOIL IS REMOVED FROM OR BROUGHT ON-SITE, THE APPLICABLE SOLID WASTE MANAGEMENT PERMIT NUMBER, EROSION SEDIMENTATION PERMIT NUMBER OR NPDES PERMIT NUMBER WILL BE RECORDED.

- GENERAL EROSION AND SEDIMENT CONTROL NOTES:**
1. ALL CONSTRUCTION SHALL COMPLY WITH ORANGE COUNTY STANDARDS AND SPECIFICATIONS.
 2. A COPY OF THE APPROVED EROSION CONTROL PLAN MUST BE ON FILE AT THE JOB SITE AT ALL TIMES.
 3. FAILURE TO FOLLOW THE APPROVED PLAN SEQUENCE AND DETAILS COULD SUBJECT THE CONTRACTOR TO FINES AND PENALTIES ISSUED.
 4. FIELD VERIFY ALL DIMENSIONS AND GRADES ON THESE PLANS PRIOR TO CONSTRUCTION. FAILURE TO NOTIFY THE OWNER OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH PLAN OR GRADE CHANGES, MAY RESULT IN NO EXTRA COMPENSATION PAID TO THE CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY.
 5. EXCAVATION AND EARTH MOVING OPERATIONS SHALL BE CONDUCTED UNDER THE SUPERVISION OF THE GEOTECHNICAL ENGINEER.
 6. VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. EXISTING UTILITIES SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND FROM A SURVEY OF ABOVE GROUND FEATURES. NO WARRANTY IS GIVEN OR IMPLIED AS TO THE ACCURACY OF THE INFORMATION. ALL EXISTING UTILITIES SHOULD BE CONSIDERED APPROXIMATE IN LOCATION AND VERIFIED PRIOR TO COMMENCING ACTIVITY ON SITE.
 7. CONTRACTOR SHALL ENSURE THAT ALL TEMPORARY DIVERSIONS ARE INSTALLED WITH POSITIVE DRAINAGE AND SHALL OPPOSE EXISTING GRADE WHEN NECESSARY TO PROVIDE A MINIMUM OF 0.5% LONGITUDINAL SLOPE.
 8. ALL ADJACENT ROADS TO THE SITE ARE TO BE SWEEPED AND WASHED AT THE END OF EACH WORK DAY TO ENSURE NO SEDIMENT COLLECTIONS ON THE ROADWAYS.
 9. INSPECT AND PROPERLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES WEEKLY AND AFTER EVERY RAINFALL EVENT.
 10. INSTALL ANY ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT SEDIMENT RUNOFF.

NPDES GROUND STABILIZATION:

SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DESTRUCTING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY GRADED ACCORDING TO THE FOLLOWING SCHEDULE:


1. ALL PERIMETER DICES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DESTRUCTING ACTIVITY.
2. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DESTRUCTING ACTIVITY.

LAND RESOURCES/SEDIMENT AND EROSION CONTROL SELF-INSPECTION PROGRAM:

1. THE SEDIMENTATION/POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DESTRUCTING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED.
2. RULES SET FORTH THE DOCUMENTATION OF THESE INSPECTIONS (W/ EFFECT OCTOBER 1, 2010).
3. THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE TOOLS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
4. EXCERPTS FROM THE NORTH CAROLINA GENERAL STATUTES AND THE NORTH CAROLINA ADMINISTRATIVE CODE CONCERNING SELF-INSPECTIONS ARE ENCLOSED, TO BETTER EXPLAIN THE REQUIREMENTS. A LIST OF FREQUENTLY ASKED QUESTIONS IS ALSO ENCLOSED ALONG WITH A SELF-INSPECTION REPORT FORM. THE SELF-INSPECTION REPORT FORM WILL ALSO BE AVAILABLE AS AN EXCEL SPREADSHEET FROM THE LAND QUALITY WEB SITE: (HTTP://OASIS.COLAQUA.UTRICH.EDU/GENERAL/LANDQUALITY/SELFINSPECTIONCONTROLFORMS)
5. PLEASE TAKE A MOMENT TO REVIEW THE ENCLOSED MATERIAL. IF YOU HAVE QUESTIONS, PLEASE CONTACT THE LAND QUALITY SECTION AT THE RALEIGH REGIONAL OFFICE.

PHASE I EROSION CONTROL CONSTRUCTION SEQUENCE:

1. A LAND DISTURBANCE PRE-CONSTRUCTION CONFERENCE IS MANDATORY BEFORE ANY WORK IS DONE AT THE SITE. ARRANGE A PRE-CONSTRUCTION MEETING WITH THE OWNER, OWNER'S ENGINEER, AND A REPRESENTATIVE FROM ORANGE COUNTY ENVIRONMENTAL SERVICES PRIOR TO LAND DISTURBING ACTIVITY. 48 HOURS NOTICE IS REQUIRED.
2. INSTALL TREE PROTECTION, SILT FENCE AND SILT FENCE OUTLETS AS SHOWN ON PLANS. ANY SEDIMENT TRACKED ON THE ROAD AS A RESULT OF THE PROJECT AND TRAFFIC FROM THE PROJECT SHALL BE REMOVED DAILY BY THE CONTRACTOR. (MINIMUM STABILIZED CONSTRUCTION ENTRANCE LENGTH=50')
3. INSTALL INLET PROTECTION ON EXISTING INLETS.
4. INSTALL EXCAVATED INLET PROTECTION AND TEMPORARY DIVERSIONS AS SHOWN ON PLANS.
5. BEGIN DEMOLITION OF EXISTING SITE FEATURES.
6. ADJUST EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY FOR PROPER OPERATION. INSTALL ADDITIONAL EROSION CONTROL MEASURES IF DETERMINED NECESSARY BY ORANGE COUNTY.
7. PROCEED TO PHASE II OF THE EROSION CONTROL SEQUENCE WHEN PHASE I MEASURES HAVE BEEN COMPLETED, INSPECTED, AND APPROVED.






NOT FOR CONSTRUCTION



PROJECT NO.	DATE
1803	DECEMBER 08, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-



SILT FENCE OUTLETS ARE TO BE PROVIDED ALONG ALL LOW POINTS OF SILT FENCE AND AREAS WHERE RUNOFF MAY CONCENTRATE CAUSING DAMAGE TO SILT FENCE. CONTRACTOR TO INSTALL OUTLETS AS NECESSARY TO ENSURE SILT FENCE IS FULLY FUNCTIONAL THROUGHOUT THE DURATION OF CONSTRUCTION.

NOTE:
THE PHASE II CONSTRUCTION PERMIT REQUIRES EROSION CONTROL DEVICES AND STORM WATER OUTFALLS BE INSPECTED WEEKLY (EVERY 7 CALENDAR DAYS) AND WITHIN 24 HRS OF A 2-INCH RAIN EVENT. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT THESE INSPECTIONS AND MAINTAIN RECORDS UNTIL THE AREA HAS STABILIZED. EVIDENT BY 85% VEGETATIVE GROWTH FOR AREAS PROVIDED SEEDING, TO FACILITATE RAINFALL MONITORING A RAIN GAUGE IS REQUIRED TO BE ON SITE. ADDITIONALLY THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING SELF-INSPECTIONS INDICATING THE DATE WHEN ARE INSTALLED AND STABILIZATION MEASURES (SEEDING/MULCHING OR SOIL) ARE INITIATED. THE "SELF-INSPECTION" REPORTS WILL BE MAINTAINED ALONG WITH THE "WEEKLY INSPECTION" REPORTS. ONCE STABILIZATION HAS BEEN ACCOMPLISHED INSPECTION RECORDS ARE TO BE FORWARDED TO EAO AND ALL TEMPORARY EROSION/SEDIMENTATION CONTROL DEVICES REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING COMPLIANCE WITH ALL PERMITS AND PLANS. ANY CHANGES WILL BE APPROVED BY THE STATE PRIOR TO EXECUTION. A COPY OF THE EROSION AND SEDIMENTATION CONTROL PLAN, LETTER OF APPROVAL, AND NPDES CONSTRUCTION PERMIT WILL BE MAINTAINED BY THE CONTRACTOR AT THE CONSTRUCTION OFFICE. IF SOIL IS REMOVED FROM OR BROUGHT ON-SITE, THE APPLICABLE SOIL WASTE MANAGEMENT PERMIT NUMBER, EROSION/SEDIMENTATION PERMIT NUMBER OR MINE PERMIT NUMBER WILL BE RECORDED.

- GENERAL EROSION AND SEDIMENT CONTROL NOTES:**
- ALL CONSTRUCTION SHALL COMPLY WITH ORANGE COUNTY STANDARDS AND SPECIFICATIONS.
 - A COPY OF THE APPROVED EROSION CONTROL PLAN MUST BE ON FILE AT THE JOB SITE AT ALL TIMES.
 - FAILURE TO FOLLOW THE APPROVED PLAN SEQUENCE AND DETAILS COULD SUBJECT THE CONTRACTOR TO FINES AND PENALTIES ISSUED.
 - FIELD VERIFY ALL DIMENSIONS AND GRADES ON THESE PLANS PRIOR TO CONSTRUCTION. FAILURE TO NOTIFY THE OWNER OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH PLAN OR GRADE CHANGES, MAY RESULT IN NO EXTRA COMPENSATION PAID TO THE CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY.
 - EXCAVATION AND EARTH MOVING OPERATIONS SHALL BE CONDUCTED UNDER THE SUPERVISION OF THE GEOTECHNICAL ENGINEER.
 - VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. EXISTING UTILITIES SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND FROM A SURVEY OF ABOVE GROUND FEATURES. NO WARRANTY IS GIVEN OR IMPLIED AS TO THE ACCURACY OF THE INFORMATION. ALL EXISTING UTILITIES SHOULD BE CONSIDERED APPROXIMATE IN LOCATION AND VERIFIED PRIOR TO COMMENCING ACTIVITY ON SITE.
 - CONTRACTOR SHALL ENSURE THAT ALL TEMPORARY DIVERSIONS ARE INSTALLED WITH POSITIVE DRAINAGE AND SHALL OPPOSE EXISTING GRADE WHEN NECESSARY TO PROVIDE A MINIMUM OF 0.5% LONGITUDINAL SLOPE.
 - ALL ADJACENT ROADS TO THE SITE ARE TO BE SWEEPED AND WASHED AT THE END OF EACH WORK DAY TO ENSURE NO SEDIMENT COLLECTIONS ON THE ROADWAYS.
 - INSPECT AND PROPERLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES WEEKLY AND AFTER EVERY RAINFALL EVENT.
 - INSTALL ANY ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT SEDIMENT RUNOFF.
 - PROVIDE ORANGE COUNTY WITH THE LOCATION OF OFFSITE STOCKPILES USED TO STORE EXCAVATED SOIL FROM THE SITE. THE LOCATION OF STOCKPILES MUST BE AN UPLAND AREA IF AN OFFSITE BORROW OR SPILL SITE IS UTILIZED. THEN THE DISTURBED AREA FOR THE BORROW/SPILL SITE MUST BE INCLUDED IN THE LAND DISTURBANCE PERMIT. THE CONTRACTOR WILL PROVIDE THE LOCATION OF ALL EXCAVATED SOILS USED FOR THIS PROJECT TO ORANGE COUNTY. THE AREA MUST ALSO BE AN UPLAND AREA.

NPDES GROUND STABILIZATION:
SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DISTURBING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY GRADED ACCORDING TO THE FOLLOWING SCHEDULE:

- ALL PERIMETER DICES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.
- ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DISTURBING ACTIVITY.

LAND RESOURCE, SEDIMENT AND EROSION CONTROL SELF-INSPECTION PROGRAM:


- THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED.
- RULES SET FORTH IN THE DOCUMENTATION OF THESE INSPECTIONS TAKE EFFECT OCTOBER 1, 2010.
- THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
- EXCERPTS FROM THE NORTH CAROLINA GENERAL STATUTES AND THE NORTH CAROLINA ADMINISTRATIVE CODE CONCERNING SELF-INSPECTIONS ARE ENCLOSED, TO BETTER EXPLAIN THE REQUIREMENTS. A LIST OF FREQUENTLY ASKED QUESTIONS IS ALSO ENCLOSED, ALONG WITH A SELF-INSPECTION REPORT FORM. THE SELF-INSPECTION REPORT FORM WILL ALSO BE AVAILABLE AS AN EXCEL SPREADSHEET FROM THE LAND QUALITY WEB SITE: <http://ocean.southcarolina.gov/central/landanderosioncontrol/erosioncontrol/faq.aspx>
- PLEASE TAKE A MOMENT TO REVIEW THE ENCLOSED MATERIAL. IF YOU HAVE QUESTIONS, PLEASE CONTACT THE LAND QUALITY SECTION AT THE RALEIGH REGIONAL OFFICE.

- PHASE II EROSION CONTROL CONSTRUCTION SEQUENCE:**
- MAINTAIN ALL EXISTING EROSION AND SEDIMENT CONTROL MEASURES PREVIOUSLY CONSTRUCTED AND ASSOCIATED WITH PHASE I AND ADJUST AS NEEDED.
 - BEGIN GRADING OF SITE AND CONSTRUCTION OF BUILDING A AND B.
 - BEGIN INSTALLATION OF STORM PIPES, WATER LINES AND SANITARY LINES.
 - INSTALL MATTING FOR SLOPES OF 3:1 OR GREATER.
 - ADJUST EROSION CONTROL MEASURES AS NEEDED.
 - PROCEED TO PHASE III OF EROSION CONTROL.

LIMITS OF DISTURBANCE: 2.08 ± AC


EROSION CONTROL LEGEND

- TEMPORARY CONSTRUCTION ENTRANCE
- SILT FENCE
- DUST CONTROL
- LINE OF DISTURBANCE
- STORAGE AREA
- STAGING AREA
- TREE PROTECTION
- SILT FENCE OUTLET
- INLET PROTECTION
- SLOPE MATTING
- DIVERSION





PROJECT NO.	DATE
1803	DECEMBER 08, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-



LIMITS OF DISTURBANCE: 2.08 ± AC

EROSION CONTROL LEGEND

- TEMPORARY CONSTRUCTION ENTRANCE
- SILT FENCE
- DUST CONTROL
- LINE OF DISTURBANCE
- TEMPORARY DRAINAGE
- STAGING AREA
- TREE PROTECTION
- SILT FENCE OUTLET
- INLET PROTECTION
- SLOPE MATTING
- SEDIMENT

SILT FENCE OUTLETS ARE TO BE PROVIDED ALONG ALL LOW POINTS OF SILT FENCE AND AREAS WHERE RUNOFF MAY CONCENTRATE CAUSING DAMAGE TO SILT FENCE. CONTRACTOR TO INSTALL OUTLETS AS NECESSARY TO ENSURE SILT FENCE IS FULLY FUNCTIONAL THROUGHOUT THE DURATION OF CONSTRUCTION.

NOTE:
THE NPDES CONSTRUCTION PERMIT REQUIRES EROSION CONTROL DEVICES AND STORM WATER OUTFALLS BE INSPECTED WEEKLY (EVERY 7 CALENDAR DAYS) AND WITHIN 24 HRS. OF A 2 INCH RAIN EVENT. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT THESE INSPECTIONS AND MAINTAIN RECORDS UNTIL THE AREA HAS STABILIZED. EVIDENT BY 95% VEGETATIVE GROWTH FOR AREAS PROVIDED SEEDING. TO FACILITATE RAINFALL MONITORING A RAIN GAUGE IS REQUIRED TO BE ON SITE. ADDITIONALLY THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING SELF INSPECTIONS INDICATING THE DATE WHEN ARE INSTALLED AND STABILIZATION MEASURES (SEEDING/MULCHING OR SOIL) ARE INITIATED. THE "SELF INSPECTION" REPORTS WILL BE MAINTAINED ALONG WITH THE "NPDES INSPECTION" REPORTS. ONCE STABILIZATION HAS BEEN ACCOMPLISHED INSPECTION RECORDS ARE TO BE FORWARDED TO EAD AND ALL TEMPORARY EROSION/SEDIMENTATION CONTROL DEVICES REMOVED. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING COMPLIANCE WITH ALL PERMITS AND PLANS. ANY CHANGES WILL BE APPROVED BY THE STATE PRIOR TO EXECUTION. A COPY OF THE EROSION AND SEDIMENTATION CONTROL PLAN, LETTER OF APPROVAL, AND NPDES CONSTRUCTION PERMIT WILL BE MAINTAINED BY THE CONTRACTOR AT THE ON-SITE OFFICE. IF SOIL IS REMOVED FROM OR BROUGHT ON-SITE, THE APPLICABLE SOLID WASTE MANAGEMENT PERMIT NUMBER, EROSION/SEDIMENTATION PERMIT NUMBER OR NINE PERMIT NUMBER WILL BE DISPLAYED.

- GENERAL EROSION AND SEDIMENT CONTROL NOTES:**
1. ALL CONSTRUCTION SHALL COMPLY WITH ORANGE COUNTY STANDARDS AND SPECIFICATIONS.
 2. A COPY OF THE APPROVED EROSION CONTROL PLAN MUST BE ON FILE AT THE JOB SITE AT ALL TIMES.
 3. FAILURE TO FOLLOW THE APPROVED PLAN SEQUENCE AND DETAILS COULD SUBJECT THE CONTRACTOR TO FINES AND PENALTIES ISSUED.
 4. FIELD VERIFY ALL DIMENSIONS AND GRADES ON THESE PLANS PRIOR TO CONSTRUCTION. FAILURE TO NOTIFY THE OWNER OF ANY DISCREPANCIES PRIOR TO PROCEEDING WITH PLAN OR GRADE CHANGES, MAY RESULT IN NO EXTRA COMPENSATION PAID TO THE CONTRACTOR FOR ANY WORK DONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY.
 5. EXCAVATION AND EARTH MOVING OPERATIONS SHALL BE CONDUCTED UNDER THE SUPERVISION OF THE GEOTECHNICAL ENGINEER.
 6. VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION. EXISTING UTILITIES SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND FROM A SURVEY OF ABOVE GROUND FEATURES. NO WARRANTY IS GIVEN OR IMPLIED AS TO THE ACCURACY OF THE INFORMATION. ALL EXISTING UTILITIES SHOULD BE CONSIDERED APPROXIMATE IN LOCATION AND VERIFIED PRIOR TO COMMENCING ACTIVITY ON SITE.
 7. CONTRACTOR SHALL ENSURE THAT ALL TEMPORARY OVERBERMS ARE INSTALLED WITH POSITIVE DRAINAGE AND SHALL OPPOSE EXISTING GRADE WHEN NECESSARY TO PROVIDE A MINIMUM OF 0.5% LONGITUDINAL SLOPE.
 8. ALL ADJACENT ROADS TO THE SITE ARE TO BE SWEEPED AND WASHED AT THE END OF EACH WORK DAY TO ENSURE NO SEDIMENT COLLECTIONS ON THE ROADWAYS.
 9. INSPECT AND PROPERLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES WEEKLY AND AFTER EVERY RAINFALL EVENT.
 10. INSTALL ANY ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO PREVENT SEDIMENT RUNOFF.
 11. PROVIDE ORANGE COUNTY WITH THE LOCATION OF OFFSITE STOCKPILES USED TO STORE EXCAVATED SOIL FROM THE SITE. THE LOCATION OF OFFSITE STOCKPILES MUST BE AN UPLAND AREA IF AN OFFSITE BORROW OR SPILL SITE IS UTILIZED. THEN THE DISTURBED AREA FOR THE BORROW/SPILL SITE MUST BE INCLUDED IN THE LAND DISTURBANCE PERMIT. THE CONTRACTOR WILL PROVIDE THE LOCATION OF ALL EXCAVATED SOILS USED FOR THIS PROJECT TO ORANGE COUNTY. THE AREA MUST ALSO BE AN UPLAND AREA.

NPDES GROUND STABILIZATION:
SOIL STABILIZATION SHALL BE ACHIEVED ON ANY AREA OF A SITE WHERE LAND-DESTRUCTING ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ACCORDING TO THE FOLLOWING SCHEDULE:


1. ALL PERIMETER DICES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1) SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 7 CALENDAR DAYS FROM THE LAST LAND-DESTRUCTING ACTIVITY.
2. ALL OTHER DISTURBED AREAS SHALL BE PROVIDED TEMPORARY OR PERMANENT STABILIZATION WITH GROUND COVER AS SOON AS PRACTICABLE BUT IN ANY EVENT WITHIN 14 CALENDAR DAYS FROM THE LAST LAND-DESTRUCTING ACTIVITY.

LAND RESOURCE/SEDIMENT AND EROSION CONTROL SELF-INSPECTION PROGRAM:

1. THE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DESTRUCTING ACTIVITIES INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED.
2. RULES SET FORTH THE DOCUMENTATION OF THESE INSPECTIONS TAKE EFFECT OCTOBER 1, 2010.
3. THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
4. EXCERPTS FROM THE NORTH CAROLINA GENERAL STATUTES AND THE NORTH CAROLINA ADMINISTRATIVE CODE CONCERNING SELF-INSPECTIONS ARE ENCLOSED. TO BETTER EXPLAIN THE REQUIREMENTS A LIST OF FREQUENTLY ASKED QUESTIONS IS ALSO ENCLOSED ALONG WITH A SELF-INSPECTION REPORT FORM. THE SELF-INSPECTION REPORT FORM WILL ALSO BE AVAILABLE AS AN EXCEL SPREADSHEET FROM THE LAND QUALITY WEB SITE. (HTTP://OAGS.CO.OLMOUNTAIN.NC.GOV/GENERAL-STATUTES-AND-ADMINISTRATIVE-CODES/EROSION-CONTROL-FAQS)
5. PLEASE TAKE A MOMENT TO REVIEW THE ENCLOSED MATERIAL. IF YOU HAVE QUESTIONS, PLEASE CONTACT THE LAND QUALITY SECTION AT THE RALEIGH REGIONAL OFFICE.

- PHASE III EROSION CONTROL CONSTRUCTION SEQUENCE:**
1. MAINTAIN ALL EXISTING EROSION AND SEDIMENT CONTROL MEASURES PREVIOUSLY CONSTRUCTED AND ASSOCIATED WITH PHASE II AND ADJUST AS NEEDED.
 2. CONTINUE GRADING OF SITE AND CONSTRUCTION OF BUILDINGS A AND B.
 3. INSTALL REMAINING UTILITIES AND ROOF DRAINS AS SHOWN ON PLANS.
 4. FINE GRADE AND INSTALL ASPHALT AND CURB AND GUTTER IN PARKING LOTS AND DRIVE AREAS AS SHOWN ON PLANS.
 5. INSTALL MATTING FOR SLOPES OF 3:1 OR GREATER.
 6. STABILIZE ALL DISTURBED AREAS PER THE PERMANENT SEEDING SPECIFICATION.
 7. AFTER SITE HAS BEEN STABILIZED AND ORANGE COUNTY INSPECTORS HAVE GIVEN FINAL INSPECTION AND APPROVAL. REMOVE REMAINING EROSION CONTROL FEATURES. ENSURE PERMANENT STABILIZATION PER THE SEEDING SPECIFICATION.









PROJECT NO.	DATE
1000	DECEMBER 8, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-






PROJECT NO.	DATE
4433	DECEMBER 8, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-



- UTILITY NOTES**
- CONTRACTOR SHALL HAVE NORTH CAROLINA ONE CALL (811) LOCATE ALL EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION.
 - ALL UNDERGROUND FEATURES INDICATED ON THE PLANS SHOULD BE CONSIDERED APPROXIMATE IN LOCATION AND SHOULD BE VERIFIED IN THE FIELD PRIOR TO CONSTRUCTION. NOTIFY THE DESIGN ENGINEER IMMEDIATELY IF ANY CONFLICTS OR DISCREPANCIES ARE NOTED.
 - CONTRACTOR SHALL COORDINATE THE LOCATION OR RELOCATION OF ALL OVERHEAD AND UNDERGROUND UTILITIES (WATER, ELECTRIC AND GAS SERVICE) WITH THE APPROPRIATE UTILITY COMPANY AND/OR THE CITY PRIOR TO BEGINNING CONSTRUCTION. CONTRACTOR SHALL PROVIDE CONDUITS AS REQUIRED FOR THESE UTILITIES UNDER PAVED AREAS.
 - ALL ILLUSTRATED UTILITY INFRASTRUCTURE IS DIAGRAMMATIC AND MAY NOT REPRESENT THE ACTUAL SIZE OF INFRASTRUCTURE. NOTIFY THE DESIGN ENGINEER IMMEDIATELY IF ANY CONFLICTS OR DISCREPANCIES ARE NOTED.
 - ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TOWN OF CHAPEL HILL, NC, AND THE STATE OF NORTH CAROLINA STANDARDS AND SPECIFICATIONS.
 - CURB STOPS ARE REQUIRED AND SHALL BE LOCATED 1 FOOT FROM THE METER BOX. CURB STOPS SHALL BE INSTALLED IN A CURB STOP BOX AS MANUFACTURED BY FISH, A.Y. HODGKINS, OR TRUMBULL.
 - SERVICE SADDLES SHALL BE ALL BRONZE WITH DOUBLE BRONZE STRAPS WITH A NEOPRENE "O" RING GASKET ATTACHED TO THE BODY.
 - ALL WATER METERS SHALL BE PROVIDED AND INSTALLED BY THE TOWN OF CHAPEL HILL, AND OVERSUA UTILITIES DEPARTMENT METERS EXCEPT.
 - METERS WILL BE THE SAME SIZE IN DIAMETER AS THE SERVICE.
 - A 3' CLEAR SPACE SHALL BE MAINTAINED AROUND ALL WATER METERS.
 - ALL 6" SANITARY SEWER SERVICES CONNECTIONS SHALL BE MADE INTO MANHOLES ONLY.
 - UTILITY TRENCHES SHALL BE CUT AND PAVEMENT REPAIRED TO THE TOWN OF CHAPEL HILL, AND OVERSUA STANDARDS.
 - ALL DISTURBED HARDSCAPE AND LANDSCAPING (CONCRETE, ASPHALT, BRICK, TREES, SHRUBS, ETC) SHALL BE REPLACED ACCORDING TO THE TOWN OF CHAPEL HILL, OVERSUA, AND NCOT STANDARDS AND SPECIFICATIONS.
 - BOUNDARY AND SURVEY INFORMATION IS TAKEN FROM A SURVEY BY TIMOTHY GROUP.
 - ALL CLEANOUTS LOCATED IN PAVED AREAS ARE REQUIRED TO BE LOCATED IN A TRAFFIC LOAD BEARING MANHOLE.
 - ALL NEW UTILITY LINES (POWER, CABLE, ETC.) MUST BE UNDERGROUND.



COMMUNITY ALTERNATIVES FOR SUPPORTIVE HOUSING
PIN: 0788106503
DB 4563 PG 470



VERTICAL GRAPHIC SCALE
1" = 5' ±

SCALE 1"=50'
0 50 100

LEGEND
 CL. EX. GRADE
 CL. F.P. GRADE
 FILL

NOTES:
 1. PIPE LENGTHS BY PROFILES ARE ACTUAL PIPE LENGTHS FROM CENTER TO CENTER OF STRUCTURE. PIPE LENGTH IN CHANGE (SLOPE BEND) ARE PIPE LENGTHS AS MEASURED IN PLAN, MEAS. FROM CENTER TO CENTER OF STRUCTURE.
 2. PROVIDE VERTICAL BENDS AT ALL WATERLINES THAT CROSS OTHER UTILITIES OR STORM PIPES WITH LESS THAN 18" OF COVER.


MOSELEYARCHITECTS
 1414 KEY HIGHWAY, BALTIMORE, MD 21220
 PHONE (410) 538-4300 FAX (410) 531-8860
 MOSELEYARCHITECTS.COM




TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

PROJECT NO.	DATE
14833	DECEMBER 8, 2011
DATE	REVISION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-


WATERLINE PROFILE
C3.2




KEY PLAN



DUMPSTER PAD B



- SOLID WASTE MANAGEMENT NOTES:**
1. PRIOR TO ANY CONSTRUCTION ACTIVITY ON SITE A PRE-CONSTRUCTION MEETING SHALL BE HELD WITH THE ORANGE COUNTY SOLID WASTE STAFF.
 2. ALL GATES SHALL INCLUDE GATE RETAINERS.
 3. BY ORANGE COUNTY ORDINANCE, CLEAN WOOD WASTE, SCRAP METAL AND CORRUGATED CARDBOARD, ALL PRESENT IN CONSTRUCTION WASTE, MUST BE RECYCLED.
 4. BY ORANGE COUNTY ORDINANCE, ALL HAULERS OF CONSTRUCTION WASTE SHALL BE PROPERLY LICENSED.
 5. IF ANY VEHICLES ARE PARKED IN THE REFUSE OR RECYCLABLES COLLECTION VEHICLE ACCESS AREA, THE CONTAINERS WILL NOT RECEIVE SERVICE UNTIL THE NEXT SCHEDULED COLLECTION DAY.




DUMPSTER PAD A

PROJECT NO.	DATE
1803	DECEMBER 8, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-



PROJECT NO.	DATE
1803	DECEMBER 08, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-



- GRADING AND STORM DRAINAGE NOTES**
- CONTRACTOR SHALL CALL NORTH CAROLINA ONE CALL (811) AT LEAST 3-12 BUSINESS DAYS PRIOR TO DIGGING TO HAVE EXISTING UTILITIES LOCATED. REPORT ANY DISCREPANCIES TO THE ENGINEER.
 - CONTRACTOR TO COORDINATE ACTIVITIES WITH UTILITY COMPANIES INVOLVED IN ANY RELATED RELOCATION (I.E. POWER POLES, TELEPHONE PEDESTALS, WATER METERS, ETC.).
 - EXISTING UTILITIES SHOWN ARE BASED ON FIELD SURVEYS AND THE BEST AVAILABLE RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY CONDITIONS PRIOR TO BEGINNING CONSTRUCTION. ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE PLANS SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY.
 - THE CATCH BASINS AND YARD INLETS SHALL BE CONSTRUCTED IN THE LOCATIONS SHOWN UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR REPORTING ANY DISCREPANCIES IN THE CATCH BASIN ELEVATIONS OR THE PROPOSED PIPE SLOPES TO THE ENGINEER. THE CONTRACTOR IS ALSO RESPONSIBLE TO REPORT ANY CONFLICTS BETWEEN ANY UTILITY, STORM DRAIN LINE, WATER LINE, SEWER LINE OR ANY OTHER PROPOSED OR EXISTING STRUCTURE TO THE ENGINEER. A LAND DISTURBING PERMIT WILL BE REQUIRED PRIOR TO THE COMMENCEMENT OF ANY LAND-DISTURBING ACTIVITIES.
 - ALL EXISTING WALLS, MANHOLES, STORM DRAIN STRUCTURES, VALVE BOXES, CLEANOUTS, ETC. SHALL BE ADJUSTED AS NEEDED TO MATCH FINISHED GRADE. ALL SLOPE, CONTRACTOR, SOILS TESTING, ETC. SHALL BE PERFORMED BY THE OWNER'S INDEPENDENT TESTING LABORATORY.
 - ALL SPOT ELEVATIONS INDICATED ARE AT TOP OF CURB UNLESS NOTED OTHERWISE. ALL ELEVATIONS ARE BASED ON VERTICAL DATUM NAVD83.
 - A PRE-CONSTRUCTION MEETING MUST BE SCHEDULED PRIOR TO ANY WORK.
 - GRADINGS OR INSTALLATION OF EROSION CONTROL MEASURES.
 - ALL HANDICAP PARKING SPACES AND STRIPED ACCESSIBILITY AREAS ARE TO HAVE NO MORE THAN A 1.50 (2.2%) SLOPE IN ALL DIRECTIONS. ALL SIDEWALKS ARE TO HAVE NO MORE THAN A 1.50 (2.2%) SLOPE FOR THE LENGTH OF THE SIDEWALK AND NO MORE THAN A 1.50 (2.2%) SLOPE FOR THE WIDTH OF THE SIDEWALK.
 - CONTRACTOR TO IDENTIFY ALL NECESSARY SPILL CURB SECTION LOCATIONS AND INSTALL TO ENSURE POSITIVE DRAINAGE TO STORM STRUCTURES. IF CONTRACTOR NOTICES ANY DISCREPANCIES IN ANY OF THESE SLOPE REQUIREMENTS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNER PRIOR TO POURING ANY CONCRETE SO THAT A SOLUTION CAN BE FOUND.
 - SPOT ELEVATIONS ARE GIVEN AT THE MAJORITY OF THE MAJOR BREAK POINTS, BUT IT SHOULD NOT BE ASSUMED THAT ALL NECESSARY SPOT ELEVATIONS ARE SHOWN. DUE TO SPACE LIMITATIONS, THERE MAY BE OTHER CRITICAL SPOTS NOT LABELED THAT SHOULD BE TAKEN INTO CONSIDERATION. THE CONTRACTOR SHALL REVIEW THE GRADING PLAN IN DETAIL AND SHALL ENSURE THAT ALL CRITICAL GRADE POINTS ARE STAKED AND FOLLOWED TO PROVIDE POSITIVE DRAINAGE.
 - EXISTING VEGETATION WITHIN TREE PROTECTIVE AREAS SHALL REMAIN UNDISTURBED UNLESS OTHERWISE INDICATED. ALL LANDSCAPING AND EXISTING TREES AND SHRUBS TO REMAIN WHICH ARE DAMAGED DURING DEMOLITION OR CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR USING A LICENSED LANDSCAPE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
 - THE GRADING CONTRACTOR SHALL COMPLY WITH ALL STATE CODES IN OBSERVING EROSION CONTROL MEASURES BOTH ON AND OFF-SITE. THE GRADING CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL DEVICES AS PER EACH MANUAL EVENT OR AS DIRECTED BY THE EROSION CONTROL INSPECTOR OR THE ENGINEER.
 - THE GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR OFF-SITE DISPOSAL OF ALL CLEANING AND GROUNDING WASTE MATERIALS GENERATED DURING CONSTRUCTION AND FOR OBTAINING ALL APPLICABLE PERMITS FOR OFF-SITE STOCKPILES AND/OR WASTE AREAS.
 - ALL CATCH BASINS MUST BE MARKED "DUMP NO WASTE DRAINS TO STREAM OR EQUIVALENT."

STORM STRUCTURE TABLE

STRUCTURE #	TOP	DESCRIPTION
CB A1	420.74	NCDOT #40.02 CONCRETE CATCH BASIN
CB A2	415.12	NCDOT #40.02 CONCRETE CATCH BASIN
CB B1	412.99	NCDOT #40.02 CONCRETE CATCH BASIN
CB B2	404.41	NCDOT #40.02 CONCRETE CATCH BASIN
CB C1	382.49	NCDOT #40.02 CONCRETE CATCH BASIN
DM A1	402.88	24 x 24 Inch Rectangular Structure
EX CE C2	365.50	24 x 24 Inch Rectangular Structure
FES A1	411.81	ES1 for 15 inch Pipe
FES A2	399.91	ES1 for 15 inch Pipe
FES C1	378.88	ES1 for 15 inch Pipe
MM A1	417.91	NCDOT #40.02 PRECAST MANHOLE
MM C1	384.87	NCDOT #40.02 PRECAST MANHOLE


STORM PIPE TABLE

PIPE #	DI	FROM - TO	UPSTREAM INVERT	DOWNSTREAM INVERT	SLOPE	LENGTH
CB A1 - MH A1	15"	CB A1 - MH A1	417.00	414.00	9.07%	33.07 LF
CB A2 - MH A1	15"	CB A2 - MH A1	412.00	411.00	1.50%	66.98 LF
CB B1 - CB B2	15"	CB B1 - CB B2	409.25	400.75	8.43%	100.86 LF
CB B2 - FES B1	15"	CB B2 - FES B1	399.75	398.40	4.85%	27.85 LF
CB C1 - MH C1	15"	CB C1 - MH C1	376.00	376.20	1.79%	44.75 LF
DM A1 - FES A2	15"	DM A1 - FES A2	399.50	398.47	1.26%	68.81 LF
EX CE C2 - MH C1	15"	EX CE C2 - MH C1	381.50	380.47	2.61%	29.69 LF
MH A1 - FES A1	15"	MH A1 - FES A1	410.80	410.37	1.50%	28.45 LF
MH C1 - FES C1	15"	MH C1 - FES C1	379.00	377.44	1.87%	28.47 LF



INSET

INSET



TOTAL AREA OF 4:1 OR GREATER SLOPES: 87,709 SF
 DISTURBED AREA OF 4:1 OR GREATER SLOPES: XXXX SF

SCALE 1"=25'
 0 25 50'



SLOPES LEGEND	
[Lightest Gray Box]	<10 PERCENT SLOPES
[Medium-Light Gray Box]	10 TO 15 PERCENT SLOPES
[Medium-Dark Gray Box]	>15 TO <25 PERCENT SLOPES
[Darkest Gray Box]	25 + PERCENT SLOPES

MOSELEYARCHITECTS
 1414 KEY HIGHWAY, BALTIMORE, MD 21220
 PHONE (410) 538-4300 FAX (410) 531-0660
 MOSELEYARCHITECTS.COM



TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

PROJECT NO.	DATE
18033	DECEMBER 8, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-

STEEP SLOPE PLAN


C4.1




NOT FOR CONSTRUCTION




PROJECT NO.	DATE
DATE	REVISION




STORM NETWORK A - PROFILE VIEW
STA. 9+80 - STA. 10+53.08




STORM NETWORK A - PROFILE VIEW
STA. 9+80 - STA. 11+19.44




STORM NETWORK A - PROFILE VIEW
STA. 9+80 - STA. 10+88.80





















STORM NETWORK B - PROFILE VIEW
STA. 9+80 - STA. 11+52.71



STORM NETWORK C - PROFILE VIEW
STA. 9+80 - STA. 10+80.88

















STORM NETWORK C - PROFILE VIEW
STA. 9+80 - STA. 10+64.73



PROJECT NO.	DATE
1201	DECEMBER 8, 2011
DATE	DESCRIPTION
-	-
-	-
-	-
-	-
-	-
-	-
-	-
-	-

NOTES AND DETAILS



MOSELEY ARCHITECTS
 1414 KEY HIGHWAY, BALTIMORE, MD 21220
 PHONE (410) 538-4300 FAX (410) 531-0660
 MOSELEYARCHITECTS.COM

TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

NOTES AND DETAILS

C5.1

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

FOR ALL BEND FITTINGS

FOR TEE FITTING

SECTION A-A

NOTES:

- Concrete blocking is to be formed to ensure accessibility to fittings and poured against undisturbed earth.
- Fittings are to be completely wrapped with plastic, prior to pouring concrete.
- Concrete to be minimum 3,000 psi @ 28 days.

ORANGE WATER AND SEWER AUTHORITY

BLOCKING DETAIL FOR HORIZONTAL BENDS AND TEE

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

TEST PRESSURE = 150 P.S.I.

PIPE SIZE (IN)	TYPE FITTING	W x H (IN)	DEPTH (IN)	VOLUME CONCRETE (CU. YD)
12"	90°	12 x 12	1.00	1.50
		12 x 12	1.00	1.50
		12 x 12	1.00	1.50
		12 x 12	1.00	1.50
45°	12 x 12	1.00	1.00	0.06
		1.00	1.00	0.06
		1.00	1.00	0.06
		1.00	1.00	0.06
TEE / PLUS	12 x 12	1.00	2.00	0.07
		1.00	2.00	0.07
		1.00	2.00	0.07
		1.00	2.00	0.07
18"	90°	18 x 18	1.00	1.50
		18 x 18	1.00	1.50
		18 x 18	1.00	1.50
		18 x 18	1.00	1.50
45°	18 x 18	1.00	1.00	0.09
		1.00	1.00	0.09
		1.00	1.00	0.09
		1.00	1.00	0.09
TEE / PLUS	18 x 18	1.00	2.00	0.10
		1.00	2.00	0.10
		1.00	2.00	0.10
		1.00	2.00	0.10
24"	90°	24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
45°	24 x 24	1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
TEE / PLUS	24 x 24	1.00	2.00	0.16
		1.00	2.00	0.16
		1.00	2.00	0.16
		1.00	2.00	0.16

CHART NOTES:

- If blocking excavation is in lightly compacted fill areas, or in areas where boulders or stumps have been removed, blocking size must be revised for the specific location/circumstance by a NC licensed Professional Engineer.
- Blocking sizes shown in these tables assume the following:
 - Blocking is constructed in residual soils as shown in detail.
 - Soil bearing pressure = 2,000 psf.
 - Velocity of flow = 15 fps.
- Neither the weight of the concrete blocking nor friction between concrete blocking and soil was added into blocking sizes computation. Therefore, blocking size is conservative.

ORANGE WATER AND SEWER AUTHORITY

BLOCKING DETAIL FOR HORIZONTAL BENDS AND TEE

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

TEST PRESSURE = 200 P.S.I.

PIPE SIZE (IN)	TYPE FITTING	W x H (IN)	DEPTH (IN)	VOLUME CONCRETE (CU. YD)
18"	90°	18 x 18	1.00	1.50
		18 x 18	1.00	1.50
		18 x 18	1.00	1.50
		18 x 18	1.00	1.50
45°	18 x 18	1.00	1.00	0.08
		1.00	1.00	0.08
		1.00	1.00	0.08
		1.00	1.00	0.08
TEE / PLUS	18 x 18	1.00	2.00	0.10
		1.00	2.00	0.10
		1.00	2.00	0.10
		1.00	2.00	0.10
24"	90°	24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
45°	24 x 24	1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
TEE / PLUS	24 x 24	1.00	2.00	0.16
		1.00	2.00	0.16
		1.00	2.00	0.16
		1.00	2.00	0.16

CHART NOTES:

- If blocking excavation is in lightly compacted fill areas, or in areas where boulders or stumps have been removed, blocking size must be revised for the specific location/circumstance by a NC licensed Professional Engineer.
- Blocking sizes shown in these tables assume the following:
 - Blocking is constructed in residual soils as shown in detail.
 - Soil bearing pressure = 2,000 psf.
 - Velocity of flow = 15 fps.
- This detail not applicable to reducing bends.
- Neither the weight of the concrete blocking nor friction between concrete blocking and soil was added into blocking sizes computation. Therefore, blocking size is conservative.

ORANGE WATER AND SEWER AUTHORITY

BLOCKING DETAIL FOR HORIZONTAL BENDS AND TEE

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

TEST PRESSURE = 250 P.S.I.

PIPE SIZE (IN)	TYPE FITTING	W x H (IN)	DEPTH (IN)	VOLUME CONCRETE (CU. YD)
24"	90°	24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
		24 x 24	1.00	1.50
45°	24 x 24	1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
		1.00	1.00	0.15
TEE / PLUS	24 x 24	1.00	2.00	0.17
		1.00	2.00	0.17
		1.00	2.00	0.17
		1.00	2.00	0.17
30"	90°	30 x 30	1.00	1.50
		30 x 30	1.00	1.50
		30 x 30	1.00	1.50
		30 x 30	1.00	1.50
45°	30 x 30	1.00	1.00	0.20
		1.00	1.00	0.20
		1.00	1.00	0.20
		1.00	1.00	0.20
TEE / PLUS	30 x 30	1.00	2.00	0.22
		1.00	2.00	0.22
		1.00	2.00	0.22
		1.00	2.00	0.22

CHART NOTES:

- If blocking excavation is in lightly compacted fill areas, or in areas where boulders or stumps have been removed, blocking size must be revised for the specific location/circumstance by a NC licensed Professional Engineer.
- Blocking sizes shown in these tables assume the following:
 - Blocking is constructed in residual soils as shown in detail.
 - Soil bearing pressure = 2,000 psf.
 - Velocity of flow = 15 fps.
- This detail not applicable to reducing bends.
- Neither the weight of the concrete blocking nor friction between concrete blocking and soil was added into blocking sizes computation. Therefore, blocking size is conservative.

ORANGE WATER AND SEWER AUTHORITY

BLOCKING DETAIL FOR HORIZONTAL BENDS AND TEE

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

FLANGE x FLANGE 90° BP BRISER

TYPICAL EYE BOLT

FLANGE x PLAN END BP BRISER

TYPICAL EYE BOLT (SEE DETAIL)

WEDGE ACTION RESTRAINER GLAND JOINT RESTRAINT

#5 REBAR x 18" O.C.

FOUR #4 3000 PSI CONCRETE @ 28 DAYS

UNDISTURBED EARTH

CONCRETE BRICK BLOCKING

SECTION A-A

NOTES:

- Excavate under slab for footing, place steel & rods in footing & pour (per #1).
- Once concrete has set in footing pour horizontal blocking (per #2).
- Footing adequate for water main up to 36" North Carolina Licensed Professional Engineer to design footings for lines greater than 36" diameter.
- Top only to be casted unless by OWSA permission.

ORANGE WATER AND SEWER AUTHORITY

THRUST FOOTING DETAIL

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

UNDISTURBED EARTH

PLAN VIEW

3,000 PSI @ 28 DAYS CONCRETE BLOCKING

UNDISTURBED EARTH

SECTION A-A

NOTES:

- Concrete blocking is to be formed to ensure accessibility to fittings and poured against undisturbed earth.
- Fittings are to be completely wrapped with plastic, prior to pouring concrete.
- Concrete to be minimum 3,000 psi @ 28 days.
- Top only to be casted unless by OWSA permission.

ORANGE WATER AND SEWER AUTHORITY

4" to 12" STANDARD TAPPING SLEEVE and VALVE ASSEMBLY

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

EX. PAV. FINISHED GRADE

BACKFILL

UNDISTURBED EARTH

PLAN VIEW

PROFILE VIEW

NOTES:

- If 42" bury depth is not maintained or located in high pressure zone, a minimum of (2) 3/4" dia. rods to be used for pipe thru 24" dia. per joint - a minimum of (2) 1" dia. rods to be used for pipe 30" & 36" dia. per joint - a minimum of (2) 1 1/4" dia. rods to be used for pipe 42" & 48" dia. per joint. (See detail 012-00)

ORANGE WATER AND SEWER AUTHORITY

STANDARD VERTICAL BEND DETAIL

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

Notes Provided by APMAC Consulting Engineers - www.apmacinc.com 06/25/2017 - 11:28:10 AM

UNDISTURBED EARTH

PLAN VIEW

PROFILE

NOTES:

- This detail depicts a typical layout. Variations may be approved.
- Service spotless may be used only an existing sewer mains. Tests / Wyes shall be used for new construction.

ORANGE WATER AND SEWER AUTHORITY

4" SEWER TAP and STUB-OUT PAVED APPLICATION CUT OUT

DATE: 06/25/2017 TIME: 11:28:10 AM

PROJECT NO: 17-001

DRAWN BY: JLD

CHECKED BY: JLD

SCALE: AS SHOWN

DATE: 06/25/2017 TIME: 11:28:10 AM

MOSELEY ARCHITECTS
 1414 KEY HIGHWAY BALTIMORE, MD 21220
 PHONE (410) 539-4300 FAX (410) 539-0660
 www.moseleyarchitects.com

N.C. STATE SEAL
 188023
 EXPIRES 12/31/2019
 NOT FOR CONSTRUCTION

TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

PROJECT NO: DATE: DECEMBER 8, 2017
 REVISIONS:
 DATE OCCURRENCE:
 .
 .
 .
 .
 .
 .
 .
 .

NOTES AND DETAILS
C5.2

GENERAL NOTES:
 USE 4000 PSI WINDHAM COMPRESSIVE STRENGTH CONCRETE.
 USE ASTM A615 GRADE 60 REINFORCING STEEL, USE ASTM A1064 WELDED WIRE FABRIC (WFF).
 FABRICATE, ASSEMBLE AND DESIGN PRECAST MANHOLE COMPONENTS ACCORDANCE WITH AASHTO W190.
 ASSEMBLE BEAMS AND BRACKETS WITH THE STEPS SPACED 12" FROM THE TOP TO THE BOTTOM OF THE MANHOLE.
 WHERE THE MANHOLE IS EXPOSED TO ROAD TRAFFIC, CONSTRUCT THE TOP OF THE MANHOLE FLUSH WITH THE GROUND AND A MINIMUM OF 6" ABOVE THE GROUND AT OTHER LOCATIONS.
 LIMIT DEPTH OF FILL TO 20'-0" FROM FINISH GRADE TO TOP OF BOTTOM SLAB.
 THE MIN. SLAB THICKNESS "T" IS THE DIMENSION OF THE THICKEST PORTION OF THE TOP-BOTTOM SLAB.
 TOP MAT OF REINFORCEMENT MAY BE SELECTED IF TOP SLAB HAS A DISTINGUISHABLE TOP AND BOTTOM.

D	W	T	A ₁
INTERNAL DIAMETER (FT.)	MIN. WALL THICKNESS (IN.)	MIN. TOP/BOTTOM SLAB THICKNESS (IN.)	MIN. CIRCUMFERENTIAL AREA OF STEEL PER VERTICAL FT. (SQ. IN.)
4	4	8	0.12
6	5	8	0.15
8	6	8	0.18

ALTERNATE CONE SECTION

TYPICAL MANHOLE SECTION

FLAT TOP SLAB

GRATED INLET OPTION

MANHOLE OPTION

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR PRECAST MANHOLE 4', 5' AND 6' DIAMETER 12" THRU 48" PIPE

SHEET 1 OF 1

840.52

GENERAL NOTES:
 USE CLASS "B" CONCRETE THROUGHOUT.
 PROVIDE ALL DROP INLETS OVER 2'-0" IN DEPTH WITH STEPS 12" ON CENTER. USE STEPS WITH COMPLY WITH STD. DRAWING 840-66.
 OPTIONAL CONSTRUCTION - MONOLITHIC FORM, 6" KEYWAY OR 4# BAR DOWELS AT 12" CENTER AS DIRECTED BY THE ENGINEER.
 USE FORMS FOR THE CONSTRUCTION OF THE BOTTOM SLAB.
 IF REINFORCED CONCRETE PIPE IS SET IN BOTTOM SLAB OF BOX, ADD TO SLAB AS SHOWN ON STD. NO. 840-25.
 CONNECT WITH PIPE DOWNHANGING.
 SET STANDARD DRAWING 840-25 FOR ATTACHMENT OF FRAMES AND GRATES NOT SHOWN.
 INSTALL 1" REINFORCER AS DIRECTED BY THE ENGINEER.
 INSTALL STONE BRICKS OF A MINIMUM OF 1" DURED EXIST OF HD. FOR STEEL AS A FINISH PANEL AND OR BRICK AT EACH STEP AND ON ALL EXTERIOR OF THE MANHOLE.
 SUMMER ALL EXPOSED CORNERS 1".
 DRAWINGS NOT TO SCALE.

PLAN

SECTION X-X

SECTION Y-Y

DOWEL

DIMENSIONS AND QUANTITIES FOR DROP INLET (BASED ON MIN. HEIGHT 3')				DIMENSIONS AND QUANTITIES FOR CONCRETE BOX		DIMENSIONS AND QUANTITIES FOR ONE PIPE	
D	A	B	H	CONCRETE	CONCRETE	CONCRETE	CONCRETE
12"	3'-0"	2'-0"	3'-0"	0.222	0.222	0.222	0.222
15"	3'-0"	2'-0"	3'-0"	0.244	0.244	0.244	0.244
18"	3'-0"	2'-0"	3'-0"	0.266	0.266	0.266	0.266
21"	3'-0"	2'-0"	3'-0"	0.288	0.288	0.288	0.288
24"	3'-0"	2'-0"	3'-0"	0.310	0.310	0.310	0.310

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR CONCRETE DROP INLET 12" THRU 30" PIPE

SHEET 1 OF 1

840.14

GENERAL NOTES:
 PROVIDE ALL CATCH BASINS OVER 3'-0" IN DEPTH WITH STEPS 12" ON CENTER. USE STEPS WITH COMPLY WITH STD. DRAWING 840-66.
 OPTIONAL CONSTRUCTION - MONOLITHIC FORM, 6" KEYWAY OR 4# BAR DOWELS AT 12" CENTER AS DIRECTED BY THE ENGINEER.
 USE FORMS FOR THE CONSTRUCTION OF THE BOTTOM SLAB.
 IF REINFORCED CONCRETE PIPE IS SET IN BOTTOM SLAB OF BOX, ADD TO SLAB AS SHOWN ON STD. NO. 840-25.
 USE TYPE "C", "D" AND "E" GRATES UNLESS OTHERWISE INDICATED.
 FOR 3'-0" IN HEIGHT OR LESS USE 6" WALLS AND BOTTOM SLAB. OVER 3'-0" TO 12'-0" IN HEIGHT USE 8" WALLS AND BOTTOM SLAB. ALWAYS QUANTITIES ACCORDANCE.
 CONNECT WITH PIPE DOWNHANGING.
 SUMMER ALL EXPOSED CORNERS 1".
 DRAWINGS NOT TO SCALE.

PLAN

ELEVATION

SECTION S-S

SECTION R-R

DOWEL

MINIMUM DIMENSIONS AND QUANTITIES FOR CONCRETE CATCH BASIN (BASED ON MIN. HEIGHT 3', WITH NO RISER)				DIMENSIONS AND QUANTITIES FOR CONCRETE BOX		DIMENSIONS AND QUANTITIES FOR ONE PIPE	
PIPE	SPAN	WIDTH	DEPTH	CONCRETE	CONCRETE	CONCRETE	CONCRETE
12"	3'-0"	2'-0"	3'-0"	0.222	0.222	0.222	0.222
15"	3'-0"	2'-0"	3'-0"	0.244	0.244	0.244	0.244
18"	3'-0"	2'-0"	3'-0"	0.266	0.266	0.266	0.266
21"	3'-0"	2'-0"	3'-0"	0.288	0.288	0.288	0.288
24"	3'-0"	2'-0"	3'-0"	0.310	0.310	0.310	0.310

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR CONCRETE CATCH BASIN 12" THRU 54" PIPE

SHEET 2 OF 2

840.02

GENERAL NOTES:
 USE CLASS "B" CONCRETE THROUGHOUT.
 PROVIDE ALL CATCH BASINS OVER 3'-0" IN DEPTH WITH STEPS 12" ON CENTER. USE STEPS WITH COMPLY WITH STD. DRAWING 840-66.
 OPTIONAL CONSTRUCTION - MONOLITHIC FORM, 6" KEYWAY OR 4# BAR DOWELS AT 12" CENTER AS DIRECTED BY THE ENGINEER.
 USE FORMS FOR THE CONSTRUCTION OF THE BOTTOM SLAB.
 IF REINFORCED CONCRETE PIPE IS SET IN BOTTOM SLAB OF BOX, ADD TO SLAB AS SHOWN ON STD. NO. 840-25.
 USE TYPE "C", "D" AND "E" GRATES UNLESS OTHERWISE INDICATED.
 FOR 3'-0" IN HEIGHT OR LESS USE 6" WALLS AND BOTTOM SLAB. OVER 3'-0" TO 12'-0" IN HEIGHT USE 8" WALLS AND BOTTOM SLAB. ALWAYS QUANTITIES ACCORDANCE.
 CONNECT WITH PIPE DOWNHANGING.
 SUMMER ALL EXPOSED CORNERS 1".
 DRAWINGS NOT TO SCALE.

PLAN

SECTION X-X

SECTION Y-Y

SECTION J-J

SECTION M-M

PLAN

PLAN

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR CONCRETE CATCH BASIN 12" THRU 54" PIPE

SHEET 1 OF 2

840.02

MOSELEY ARCHITECTS
 1414 KEY HIGHWAY BALTIMORE MD 21220
 PHONE (410) 584-3400 FAX (410) 531-0960
 MOSELEYARCHITECTS.COM


NOT FOR CONSTRUCTION

TRINITY COURT
 TRINITY COURT REDEVELOPMENT, LLC
 751 TRINITY CT, CHAPEL HILL, NC 27516

PROJECT NO. DATE: DECEMBER 8, 2021
 REVISIONS:
 DATE DESCRIPTION

NOTES AND DETAILS

C5.3



LANDSCAPE REQUIREMENTS - TREE CANOPY COVERAGE




TREE CANOPY MEASUREMENT:
 TOTAL LOT SIZE: 3.22 AC (140,777 SF)
 TOTAL BUFFER AREA: 0.425 AC (18,513 SF)
 BUFFER AREA NOT COVERED WITH EXISTING TREES: 0.055 AC (2,403 SF)
 2,403 (10) x 2.01 LF BUFFER TO BE PLANTED
 240 / 100 LF = 3
 3 x 4 = 12 LARGE TREES TO BE PLANTED
 3 x 7 = 21 SMALL TREES TO BE PLANTED
 3 x 12 = 36 SHRUBS TO BE PLANTED

REQUIRED CANOPY COVERAGE:
 140,777 SF x 33% = 46,257 SF
 TOTAL REQUIRED TREE COVERAGE = 42,233 SF (0.97 AC)


EXISTING CANOPY TO BE PROTECTED:
 AREA 'A' = 0.7 AC (30,450 SF)
 AREA 'B' = 0.45 AC (19,741 SF)
 AREA 'C' = 0.05 AC (2,403 SF)
 TOTAL EXISTING CANOPY = 1.21 AC (52,594 SF)

CANOPY COVERAGE:
 CANOPY COVERAGE REQUIRED (30%) 42,233 SF
 CANOPY COVERAGE PROVIDED (37.3%) 52,594 SF

- TOWN STANDARD TREE PROTECTION NOTES:**
- A PRE-CONSTRUCTION CONFERENCE WILL BE HELD WITH THE TOWN'S URBAN FORESTER PRIOR TO BEGINNING SITE WORK.
 - ANY TREE ROOTS EXPOSED BY CONSTRUCTION WILL BE SEVERED CLEANLY WITH AN APPROPRIATE
 - THE SOIL WITHIN THE CRITICAL ROOT ZONES OF EXISTING TREES WILL NOT BE DRIVEN ON OR OTHERWISE DISTURBED DURING THE INSTALLATION OF LANDSCAPING.
 - A LANDSCAPE PROTECTION SUPERVISOR WHO IS REGISTERED WITH THE TOWN OF CHAPEL HILL WILL BE PRESENT ON SITE AT ALL TIMES WHEN THE FOLLOWING ACTIVITIES ARE TAKING PLACE: CLEARING, GRUBBING, EXCAVATION, GRADING, TRENCING, MOVING OF SOIL, INSTALLATION AND REMOVAL OF TREE PROTECTION FENCING, AND THE DELIVERY, TRANSPORTING AND PLACEMENT OF CONSTRUCTION MATERIALS AND EQUIPMENT.
 - TO PROPERLY PROTECT AND ENSURE THE HEALTH OF EXISTING TREES TO REMAIN, PROTECTIVE FENCING SHOULD BE INSTALLED TO PROTECT NO LESS THAN 75% OF A TREE'S CRITICAL ROOT ZONE. WHEN ERECTING FENCING NEAR TREES THAT ARE NOT INDIVIDUALLY IDENTIFIED ON THE LANDSCAPE PROTECTION PLAN, THE FENCING LOCATION SHOULD BE SITED, WHERE POSSIBLE, ON A TREE REMOVED BY ITS CRITICAL ROOT ZONE IS NOT ADEQUATELY PROTECTED. ALL LAND DISTURBING ACTIVITY, STORAGE OF EQUIPMENT, BUILDING MATERIAL, SOIL AND OTHER DEBRIS SHOULD BE KEPT WITHIN THE AREA OF DEVELOPMENT ACTIVITY AND OUTSIDE OF THE PROTECTIVE FENCING. THE TOWN'S STANDARD FOR TREE PROTECTION FENCING IS TO BE CHANGED TO WOVEN PLASTIC OR FABRIC WITH A HEIGHT OF FOUR (4) FEET INSTALLED ON METAL POSTS SET A MINIMUM OF TEN (10) FEET APART AS SHOWN IN THE FOLLOWING TYPICAL DETAIL.



PROJECT NO: 20210818
 DATE: DECEMBER 8, 2021
 DRAWN BY: [Signature]
 CHECKED BY: [Signature]



PLANTING CALCULATIONS:
(DESIGN MANUAL SEC. 3)

PARKING LOTS

SHADING REQUIREMENTS:

- 1 LARGES TREE PER 2,000 SF OF PAVING
- TREES TO BE PLANTED WITHIN 10' OF PARKING LOT EDGE
- NO PARKING SPACE FURTHER THAN 60' FROM LARGE TREE TRUNK OR FARTHER THAN 75' FROM 2 LARGE TREES

LARGE TREE PLACEMENT:

- 3.5' FROM BACK OF CURB, EDGE STREET PAVEMENT, DRIVEWAYS, SIDEWALKS
- 10' FROM BUILDINGS
- 15' FROM STREET LIGHTS, UTILITY POLES
- 10' FROM UTILITY VAULTS

SMALL TREE PLACEMENT:

- 3.5' FROM BACK OF CURB, EDGE STREET PAVEMENT, DRIVEWAYS, SIDEWALKS
- 2.5' FROM SIDEWALKS AND PAVED PEDESTRIAN SURFACES
- 5' FROM BUILDINGS
- 10' FROM STREET LIGHTS, UTILITY POLES
- 5' FROM UTILITY VAULTS AND UNDERGROUND UTILITIES

TOTAL PAVEMENT AREA (INCLUDES LOT AND DRIVE) = 26,318 SF
PARKING LOT PAVEMENT AREA = 10,645
10,645 SF / 2,000 SF = 5 TREES

REQUIRED = 6 LARGE TREES
PROVIDED = 6 LARGE TREES

***EXISTING TREES TO COUNT TOWARDS LANDSCAPE REQUIREMENTS AS FEASIBLE AT THE DIRECTION OF THE PLANNING DIRECTOR.**

SCREENING REQUIREMENTS:

- EXISTING SCREENING MIN. HT. OR 2' AT PLANTING FOR 3' TALL SCREENING, 3' FOR 4' TALL SCREENING
- SCREEN UTILITY SERVICE FROM PUBLIC RIGHT-OF-WAY

BUFFER CALCULATIONS:

BUFFER TYPE "B"
TOTAL BUFFER AREA: 0.425 AC (18,513 SF)
PLANTABLE BUFFER AREA NOT COVERED WITH EXISTING TREES: 0.255 AC (10,403 SF, 240 LF)

REQUIREMENTS PER 100 LF INTERNAL 10' WIDE:



- (4) LARGE TREES
- (7) SMALL TREES
- (12) SHRUBS

2,403 / 10 = 240 LF BUFFER TO BE PLANTED
240 / 100 LF = 3

3 x 4 = 12 LARGE TREES REQUIRED,
+ 12 LARGE TREES PROVIDED

3 x 7 = 21 SMALL TREES REQUIRED,
+ 21 SMALL TREES PROVIDED

3 x 12 = 36 SHRUBS REQUIRED,
+ 36 SHRUBS PROVIDED



PROJECT NO.	DATE
10000	DECEMBER 8, 2011
DATE	DESCRIPTION
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED
11/15/11	REVISED

